BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/09/2018-19 Dated: 27-2-2019

APPROVED TENDER SCHEDULE –'B'

Item-51

Name of Work:-Improvements to drains at Kaveri Layout in ward no 03, Attur

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri SAMBASHIVA REDDY C	
				Rate	Rate in Words
1	KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 Page No. 143 / Item No. 19.1, PWD SR 2018-19	Cum	233.70	232.87	Rupees Two Hundred Thirty Two and Paise Eighty Seven Only
2	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. Page No.13, Item No. 4.3 of PWD SR 2018-19	Cum	36.90	5043.07	Rupees Five Thousand Forty Three and Paise Seven Only
3	Providing and laying cement concrete using 20 mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) M 20 for R.C.C works laid in 15 cms thick layers and well compacted vibrating, curing, for raft foundation column footing , main and secondary beams with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Page No. 18, Item No. 4.48 PWD SR 2018-19	Cum	77.49	5381.12	Rupees Five Thousand Three Hundred Eighty One and Paise Twelve Only
4	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of	Tonne	4.65	70146.34	Rupees Seventy Thousand One Hundred Forty Six and Paise Thirty Four Only

Sl No	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri SAMBASHIVA REDDY C	
				Rate	Rate in Words
5	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 Page No. 16 / Item No. 4.31 PWD SR 2018-19	Sqm	590.40	353.00	Rupees Three Hundred Fifty Three Only
6	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. Page No.13, Item No. 4.6 PWD SR 2018-19	Cum	7.38	5359.38	Rupees Five Thousand Three Hundred Fifty Nine and Paise Thirty Eight Only
7	Providing precast slab of 100mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc., complete as per the direction of engineer in charge - Data rate	Sqm	197.64	2179.25	Rupees Two Thousand One Hundred Seventy Nine and Paise Twenty Five Only

G. Samba Shiva Reddy
Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.